



Scale: 1:1500

Address: 10660 Highway 97 Lake Country B.C. District of Lake Country Zoning: RM2 Landscape Statistics 20,101.20 sq m 9,933.33 sq m 49.42 % of site

provided 179 125.00 Deciduous Trees 54.00 Coniferous Trees 54.00 provided 505.00

Deciduous

Coniferous

259.00

• Sod areas are limited to the central ammenity areas to a maximum of 2,000 sq.m.. the remainder of the site will be landscaped with drought tolerant ground covers and plant material.

Central community areas for planting beds equal a total

Plant List Qty Common Name

Botanical Name Ornamental Grasses and Groundcovers

> Calamagrostis x acutiflora 'Avalanche' Miscanthus sinensis 'Purpurascens'

Blue Carpet Juniper Dwarf Mugo Pine Pinus mugo 'pumilio' Perovskia atriplicifolia

Amber Jubilee Ninebark Arctic Fire Red Twig Dogwood Cornus sericea 'Farrow' Double play candy corn spirea Spiraea japonica 'candy corn' Physocarpus opulifolius 'Donna May' Little Devil Ninebark

113 Red-osier Dogwood 109 Snowberry

Bowhall Maple Crimson spire oak Dakota Pinnacle Birch Lone Star Linden

Patmore Green Ash

Platanus x acerifolia 'Bloodgood' Acer rubrum 'bowhall' Tilia cordata

Cornus sericea

Symphoricarpos albus

Fraxinus pennsylvanica 'Patmore'

Quercus robur 'crimschmidt' Betula platyphylla 'Fargo' Ivory Silk Japanese Tree Lilac Syringa reticulata 'Ivory Silk'

amber jubilee ninebark red twig dogwood candy com spirea little devil ninebark mottled dogwood

oso easy paprika rose

red-osier dogwood

snowberry

88

russian sage

Drawing Title:

Drawn by:

landscape areas

Site Information

Site Area Phase 1-3 Landscape area provided 1 tree per 60 sq m Shurbs 1 Shrubs per 30 sq m

Site Notes:

area of 310 s.q.m

329 Bronze Veil Tufted Hair Grass Deschampsia caespitosa 'Bronzeschleier' 203 Avalanche Reed Grass 121 Flame Grass 129 Prairie Fire Red Switch Grass Panicum virgatum 'Prairie Fire'

Shrubs Coniferous

Juniperus squamata 'Blue Carpet' 128 Russian Sage Physocarpus opulifolius 'Jefam'

Mottled Dogwood Cornus alba 'Gouchaultii' Rosa sp ' Oso Paprika' Oso Easy Paprika Rose

Trees

Coniferous Interior Douglas Fir Pseudotsuga menziesii 27 Yellow Ponderosa Pine Pinus ponderosa Deciduous Bloodgood London Plane

Trembling Aspen Populus tremuloides

min 2.5m height bloodgood london plane min 60 mm cal bowhall maple min 60 mm cal

yellow ponderosa pine



trembling aspen min 60 mm cal dakota pinnade birch min 60 mm cal

japanese tree lilac

groundcovers

bronze veil tufted grass avalanche reed grass

flame grass prairie fire red switch grass

wood mulch sod limited to central amenty area

drought tolerant and flowering seed mix sheep fescue bluebunch wheetgrass perennial rye grass micro-clover English daisy roman chamomile baby blue eyes

shrubs

concrete paving accent colour concrete DP blue carpet juniper review and coordination DP dwarf mugo pine review and coordination

Project No. 23-001

Issued for:

Project Title. Lake Country Townhouses

24.01.16

23.10.11

23.10.10

23.07.11

23.06.08

Date. (yy.mm.dd)

Attachment C-DP000802-Landscape Plan

arquiecos

General Notes

Representative.

of Arquiecos Group Ltd.

specifically issued as such.

discreptancies immediately.

Owner's Representative

immediately.

Irrigation Notes

1. This drawing, including all concepts and design ideas are property

This drawings can only be reproduced with writen authorization of

2. These drawings must not be used for construction purposes unless

Due to printing and reproduction scale may vary slightly. Written

Contractors to verify all dimensions, datum, elevations and

4. Any variatons and design changes to the information shown on

5. Any references made to the location of all existing and proposed

authorization from Arquiecos Grup Ltd. the Project Owner or the

grading on site prior to commencing work. Report any

these drawings must not be carried out without written

utilities, including URW must be verified on site prior to

comencing work. Report any and all conficts identified

6. Contractor must adhere to municipal, provincial and federal

regulations, guidelines and by-laws including but not limited to the most recent versions of the Canadian Standards for Nursery

Stock as well as municipal Landscape and Roads Construction

Any discrepancies between municipal standards and details

presented in these drawings must be reported immediately.

Municipal Construction standards rule over these drawings.

irrigation system as per municipal standards.

location of power and water sources.

only if required thereafter.

Key Plan

1. All landscape areas shall be watered by an automatic underground

Contractor is responsible for coordination with other trades and

subconsultants regarding the specifics of the system, including

Ensure power and water meters are properly installed and

2. Sod areas to include high efciciency irrigation system with MP

Spray Irrigation for seeded areas to run untill establishment and

Arquiecos Group, the Project Owner or the Owner's

titleblock and viewports. Do not scale drawings.

dimensions rule over scaled dimensions

This drawings have been drawn to scale as indicated in the

Arquiecos Group Ltd. Design and Development Consultants

8-121 Village Heights SW Calgary, Alberta T3H 2L2

p. 403.618.44.27 e. info@arquiecos.com

10660 Highway 97 Lake Country, B.C.


Overall Plan

Drawing No. Checked by:



Attachment C-DP000802-Landscape Plan

This drawings can only be reproduced with writen authorization of



	Issued for:	Date. (yy.mm.dd
4	review and coordination	23.06.08
5	DP	23.07.11
6	review and coordination	23.10.10
7	DP	23.10.11
8	DP	24.01.16





2 Central Courtyard South
Scale: 1:175

Site furnishings



Landscapeforms Link bench metal legs, curved , back and arms Titanium Powder coat



Surface mount



Landscapeforms Emerson bikerack Earthscape Tot lot equipment or approved similar final design TBD Titanium Powder coat



Landscapeforms Typology light bollard Surface mount Titamium Powder coat Natural grey concrete

Attachment C-DP000802-Landscape Plan



trees

yellow ponderosa pine

bloodgood london plane

min 2.5m height

min 60 mm cal

bowhall maple min 60 mm cal

crimson spire oak min 60 mm cal

Ionestar linden min 60 mm cal

patmore green ash min 60 mm cal

trembling aspen min 60 mm cal

min 60 mm cal

groundcovers

flame grass

wood mulch

sheep fescue

micro-clover

 English daisy roman chamomile baby blue eyes

shrubs

concrete paving accent colour concrete

blue carpet juniper

amber jubilee ninebark

red twig dogwood

candy com spirea

little devil ninebark

mottled dogwood

red-osier dogwood

red-osier do

oso easy paprika rose

russian sage

dakota pinnade birch

japanese tree lilac min 60 mm cal

bronze veil tufted grass

avalanche reed grass


prairie fire red switch grass

limited to central amenty area

Arquiecos Group Ltd. Design and Development Consultants 8-121 Village Heights SW Calgary, Alberta T3H 2L2 p. 403.618.44.27

e. info@arquiecos.com





General Notes

This drawing, including all concepts and design ideas are property

Representative.

of Arquiecos Group Ltd. This drawings can only be reproduced with writen authorization of Arquiecos Group, the Project Owner or the Owner's

2. These drawings must not be used for construction purposes unless specifically issued as such.

3. This drawings have been drawn to scale as indicated in the titleblock and viewports. Do not scale drawings. Due to printing and reproduction scale may vary slightly. Written

dimensions rule over scaled dimensions Contractors to verify all dimensions, datum, elevations and grading on site prior to commencing work. Report any discreptancies immediately. 4. Any variatons and design changes to the information shown on

these drawings must not be carried out without written authorization from Arquiecos Grup Ltd. the Project Owner or the Owner's Representative 5. Any references made to the location of all existing and proposed

drought tolerant and utilities, including URW must be verified on site prior to flowering seed mix comencing work. Report any and all conficts identified bluebunch wheetgrass 6. Contractor must adhere to municipal, provincial and federal regulations, guidelines and by-laws including but not limited to perennial rye grass

> Stock as well as municipal Landscape and Roads Construction Any discrepancies between municipal standards and details presented in these drawings must be reported immediately.

the most recent versions of the Canadian Standards for Nursery

Municipal Construction standards rule over these drawings.

Irrigation Notes


only if required thereafter.

1. All landscape areas shall be watered by an automatic underground irrigation system as per municipal standards. Contractor is responsible for coordination with other trades and subconsultants regarding the specifics of the system, including location of power and water sources.

Ensure power and water meters are properly installed and operating prior to utilization of the system.

2. Sod areas to include high efciciency irrigation system with MP

Spray Irrigation for seeded areas to run untill establishment and



24.01.16 23.10.11 23.10.10 6 review and coordination 23.07.11 23.06.08 review and coordination

23-001

Issued for:

Project Title. Lake Country Townhouses


Date. (yy.mm.dd)

10660 Highway 97 Lake Country, B.C.


Drawing Title:

Central Courtyard Plan


cmp Checked by: jj / cmp



west boulevard Scale: 1:125



central boulevard 2 central bo



east boulevard 3 east boule Scale: 1:125



























groundcovers





prairie fire red switch grass





flowering seed mix sheep fescue bluebunch wheetgrass

 English daisy • roman chamomile baby blue eyes


blue carpet juniper
dwarf mugo pine


russian sage

amber jubilee ninebark

candy com spirea

little devil ninebark





Attachment C-DP000802-Landscape Plan

arquiecos

General Notes

Representative.

of Arquiecos Group Ltd.

specifically issued as such.

discreptancies immediately.

Owner's Representative

immediately.

Irrigation Notes

This drawing, including all concepts and design ideas are property

This drawings can only be reproduced with writen authorization of

These drawings must not be used for construction purposes unless

Due to printing and reproduction scale may vary slightly. Written

3. This drawings have been drawn to scale as indicated in the

Contractors to verify all dimensions, datum, elevations and grading on site prior to commencing work. Report any

4. Any variatons and design changes to the information shown on these drawings must not be carried out without written

authorization from Arquiecos Grup Ltd. the Project Owner or the

5. Any references made to the location of all existing and proposed

utilities, including URW must be verified on site prior to comencing work. Report any and all conficts identified

6. Contractor must adhere to municipal, provincial and federal

regulations, guidelines and by-laws including but not limited to

the most recent versions of the Canadian Standards for Nursery

Stock as well as municipal Landscape and Roads Construction

Any discrepancies between municipal standards and details

presented in these drawings must be reported immediately.

Municipal Construction standards rule over these drawings.

irrigation system as per municipal standards.

location of power and water sources.

only if required thereafter.

operating prior to utilization of the system.

1. All landscape areas shall be watered by an automatic underground

Contractor is responsible for coordination with other trades and subconsultants regarding the specifics of the system, including

Ensure power and water meters are properly installed and

2. Sod areas to include high efciciency irrigation system with MP

spray heads. Spray Irrigation for seeded areas to run untill establishment and

Arquiecos Group, the Project Owner or the Owner's

titleblock and viewports. Do not scale drawings.

dimensions rule over scaled dimensions

Arquiecos Group Ltd. Design and Development Consultants

8-121 Village Heights SW Calgary, Alberta T3H 2L2 p. 403.618.44.27 e. info@arquiecos.com

24.01.16 23.10.11 DP 23.10.10 review and coordination 23.07.11 23.06.08 review and coordination Date. (yy.mm.dd) Issued for:

Project No.

Lake Country Townhouses

10660 Highway 97 Lake Country, B.C.

Boulevard landscape plans


L-3































 perennial rye grass micro-clover





concrete paving

dwarf mugo pine

red twig dogwood

mottled dogwood



Qty Unit		Unit Cost	Comments	Total
125	each	\$900	Supply and Install, Includes Topsoil, bark mulch and 2 year warranty.	\$ 112,500
54	each	\$900	Supply and Install, Includes Topsoil, bark mulch and 2 year warranty.	\$ 48,600
505	each	\$65	Supply and Install, Includes Topsoil, bark mulch and 2 year warranty.	\$ 32,825
259	each	\$65	Supply and Install, Includes Topsoil, bark mulch and 2 year warranty.	\$ 16,835
782	each	\$35	Supply and Install, Includes Topsoil, bark mulch and 2 year warranty.	\$ 27,370
2000	sq. m.	\$10	Including 15mm of topsoil and grading	\$ 20,000
2120	sq.m.	\$8	Hydroseed including colour tachifier, 150mm of topsoil and grading	\$ 16,963
4114	sq.m.	\$10	fine ground wood mulch	\$ 41,135
1208	sq.m.	\$20	25-40mm decorative rock mulch with filter fablic underlay	\$ 24,154
1	allow	\$130,000	Irrigation System with high efficiency MP spray heads, and bubblers for trees. Design Build by contractor to be reviewed and approved by Landscape Architect.	\$ 130,000
			Subtotal	\$ 470,383
441	sq.m.	\$110	125mm thick concrete paving with rebar or wire mesh. Broom finish with sawcut control joints at 1.5-2.0m O.C.	\$ 48,552
113	sq.m.	\$115	125mm thick concrete paving with rebar or wire mesh. Broom finish with sawcut control joints at 1.5-2.0m O.C. Interstar colour Black Onyx (2 bags)	\$ 13,046
28	sq.m.	\$2,000	Poured in place concrete walls with rebar wire reinforcement . Contractor to provide engineering drawings for review	\$ 55,010
			Subtotal	\$ 116,608
406	l. m.	\$150	Wood Screen fence as per contract documents 1.80m (6') height.	\$ 60,875
8	each	\$1,800	benches as per drawings	\$ 14,400
8	each	\$1,000	bike racks as per drawings	\$ 8,000
58	each	\$650	bollards as per drawings	\$ 37,700
43		\$350	300mm high wood planter boxes for community gardening on grade	\$ 15,050
1		\$95,000	tot lot equipment and safety surfacing as per landscape plans	\$ 95,000
			Subtotal	\$ 231,025
	54 505 259 782 2000 2120 4114 1208 1 441 113 28	54 each 505 each 259 each 782 each 2000 sq. m. 2120 sq.m. 4114 sq.m. 1208 sq.m. 1 allow 441 sq.m. 128 sq.m. 1 bq.m. 1 sq.m. 1 sq.m. 1 allow	54 each \$900 505 each \$65 259 each \$65 782 each \$35 2000 sq. m. \$10 2120 sq.m. \$8 4114 sq.m. \$10 1208 sq.m. \$20 1 allow \$130,000 441 sq.m. \$115 28 sq.m. \$2,000 406 l. m. \$150 8 each \$1,800 8 each \$1,000 58 each \$650 43 each \$350	54 each \$900 Supply and Install, Includes Topsoil, bark mulch and 2 year warranty. 505 each \$65 Supply and Install, Includes Topsoil, bark mulch and 2 year warranty. 259 each \$65 Supply and Install, Includes Topsoil, bark mulch and 2 year warranty. 782 each \$35 Supply and Install, Includes Topsoil, bark mulch and 2 year warranty. 2000 sq. m. \$10 Including 15mm of topsoil and grading 2120 sq.m. \$8 Hydroseed including colour tachifier, 150mm of topsoil and grading 4114 sq.m. \$10 fine ground wood mulch 1208 sq.m. \$20 25-40mm decorative rock mulch with filter fablic underlay 1 allow \$130,000 Irrigation System with high efficiency MP spray heads, and bubblers for trees. Design Build by contractor to be reviewed and approved by Landscape Architect. Subtotal 441 sq.m. \$110 125mm thick concrete paving with rebar or wire mesh. Broom finish with sawcut control joints at 1.5-2.0m O.C. 113 sq.m. \$115 125mm thick concrete paving with rebar or wire mesh. Broom finish with sawcut control joints at 1.5-2.0m O.C. Interstar colour Black Onyx (2 bags) 28 sq.m. \$2,000 Poured in place concrete walls with rebar wire reinforcement . Contractor to provide engineering drawings for review Subtotal 406 I. m. \$150 Wood Screen fence as per contract documents 1.80m (6') height. 8 each \$1,800 benches as per drawings 91,000 bike racks as per drawings 158 each \$650 bollards as per drawings 159 each \$350 300mm high wood planter boxes for community gardening on grade 1595,000 tot lot equipment and safety surfacing as per landscape plans

Notes.

- 1. This is a preliminary opinion of probable costs based on development permit design plans, not a guaranteed cost figure.
- 2. Contractors are responsible for accurate quantity calculations and field measurements.
- 3. Cost estimate does not include; haulage, maintenance, unforeseen site conditions, and other costs associated with construction phasing and staging.
- 4. All costs include supply and installation unless otherwise noted.
- 5. All costs are exclusive of GST.


Attachment C-DP000802-Landscape Plan



Arquiecos Group Ltd. Design and Development Consultants arquiecos 8-121 Village Heights SW Calgary, Alberta T3H2L2 p. 403.618.44.27

e. info@arquiecos.com





General Notes

1. This drawing, including all concepts and design ideas are property of Arquiecos Group Ltd.

- This drawings can only be reproduced with writen authorization of Arquiecos Group, the Project Owner or the Owner's Representative.
- 2. These drawings must not be used for construction purposes unless specifically issued as such.
- 3. This drawings have been drawn to scale as indicated in the titleblock and viewports. Do not scale drawings. Due to printing and reproduction scale may vary slightly. Written
- dimensions rule over scaled dimensions Contractors to verify all dimensions, datum, elevations and grading on site prior to commencing work. Report any discreptancies immediately.
- 4. Any variations and design changes to the information shown on these drawings must not be carried out without written authorization from Arquiecos Grup Ltd. the Project Owner or the Owner's Representative
- 5. Any references made to the location of all existing and proposed utilities, including URW must be verified on site prior to comencing work. Report any and all conficts identified
- immediately. 6. Contractor must adhere to municipal, provincial and federal regulations, guidelines and by-laws including but not limited to the most recent versions of the Canadian Standards for Nursery Stock as well as municipal Landscape and Roads Construction
- Standards. Any discrepancies between municipal standards and details presented in these drawings must be reported immediately. Municipal Construction standards rule over these drawings.

Irrigation Notes 1. All landscape areas shall be watered by an automatic underground

- irrigation system as per municipal standards. Contractor is responsible for coordination with other trades and subconsultants regarding the specifics of the system, including location of power and water sources. Ensure power and water meters are properly installed and
- operating prior to utilization of the system.

 2. Sod areas to include high efciciency irrigation system with MP

spray heads.

Spray Irrigation for seeded areas to run untill establishment and only if required thereafter.

Key Plan

8	DP	24.01.16
7	DP	23.10.1
6	review and coordination	23.10.10
5	DP	23.07.1
4	review and coordination	23.06.08
	Issued for:	Date. (yy.mm.do

Lake Country Townhouses

10660 Highway 97 Lake Country, B.C.

Drawing Title:

Cost Estimate